

SZ-200

Warranty

- ◆ 5 years Manufacturer Warranty
- ◆

Manufacturing

- ◆ Original cell sorting system ensures the best electric cell match
- ◆ EL-Testing before packing.
- ◆ Comprehensive module power testing.

Performance

- ◆ Higherer module efficiency and compact size. Weakened hot-spot effect, lower module failure rate and increased stability by shingle-tech.
- ◆ Special connection method lowers the internal resistance and ensures better performance than traditional connection with busbar.
- ◆ IP67 rated junction box, reliable cables and standard MC4 connectors improve the stability



Mechanical Data

Standard Test Conditions AM=1.5, E=1000W/m², TC=25°C

Nominal Power	200W
Cell Type	Monocrystalline
Cell Efficiency	22%
Maximum Power Current (Impp)	8.21A
Maximum Power Voltage (Vmpp)	24.36V
Open-circuit Voltage (Voc)	28.56V
Short-circuit Current (Isc)	8.71A
Maximum System Voltage	500V
Output Tolerance	0~+3%
Cable	700mm / 2.5mm ²
Connector Type	MC4 / MC4 Compatible
Module Structure	Aluminum Frame / Glass / EVA / Backsheet
Junction box rating	IP67
Diode	
Working Temperature	-40~+80°C

Packaging

Module Dimensions	1530*670*30mm
Module Weight	10.2 kg
Package	Single Package
Pieces per Pallet	30pcs
Gross Weight per Pallet	380kg
Pallet Dimensions	1530*1100*800mm

SOLMAX NEW ENERGY B.V.

Address: Defensiedok 18,3433 KL, Nieuwegein, The Netherlands

Tel: +31-307855708

info25@solarfam.nl

